

Technician Bulletin—Troubleshooting for CK1543

Undercounter Dishwashers

A common problem, that our customers report, is due to poor maintenance of the air trap.

The air trap is located on the back wall inside the washing chamber (Pic 1). A build up of dirt behind the metal protection means the machine may either over or under fill.

This problem ISN'T covered by our warranty due to lack of maintenance.

To solve the problem simply remove the 2 metal nuts, give the area a quick wipe and replace (Pic 2). This only needs completing monthly.

Pic 1



Pic 2

